

ADDENDUM #4

Will County Health Department BID PACKAGE #2 – Misc. Steel/Structural/Enclosure November 09, 2018

This addendum will be included in all future sets of drawings distributed and on the Leopardo Building Connected website.

Division 1 – General Instructions

1.0 Bid Instructions

A. Bid Submission

1. <u>All Bid Categories' Bid Due Date is Extended to Tuesday November 20, 2018 1:00PM and Will Be Publicly Opened in the Will County Board Committee Room, 302 N. Chicago Street, Joliet, IL 60432.</u>

1.1 Bid Documents

A. Schedule of Bid Documents

The following documents are included as part of this bid addendum:

DATE	DESCRIPTION	By
11/09/18	Addendum Narrative (this document) - FOLLOWS – 1 Page	Leopardo
		Companies
11/09/18	2-06 Structural Steel Scope of Work REVISION – FOLLOWS	Leopardo
		Companies

2.0 General Information

A. Revised 2-06 Structural Steel Scope of Work

- Revise item 7) a. as follows:
 - Provide OSHA approved safety cabling at perimeter of all floors including roof and at all deck. Maintain cabling until specific area of the project is released for the work of other trades. Steel sub to maintain during construction. Toe boards shall be furnished and installed by the Concrete contractor including toe board maintenance. Provide perimeter roof cabling as required by OSHA for steel erection. Steel Subcontractor to furnish and install all steel stranded cable system at the perimeter of the building. The safety rails shall be independently arranged so that the rails can only be removed from column to column affecting the adjacent rails on the floor or next to the removed rails. Each column shall be punched to accept steel guardrail system. Provide and install complete guardrail system to structurally withstand all associated loads for this subcontractor's scope of work This subcontractor must provide all cabling turn buckles, engineering and etc. for a complete guard rail system. Removal of toe board and attachment is to be by Miscellaneous Steel Subcontractor. Removal and salvage of safety cable is to be by Miscellaneous Steel Subcontractor. Coordinate with Site Superintendent.